

#### **IV) GASIFICATION OF THE MUNICIPALITY OF ČIČEVAC**

under construction, 2025 – present

A) Planned length of distribution gas pipeline network, operating pressure up to 4 bar:  
approx. 152 km

B) Planned length of distribution gas pipeline network, operating pressure up to 16 bar:  
approx. 12.5 km

C) Planned construction of metering and regulation stations (16/4 bar): 4 units

D) Planned construction of customer (household) gas connections: 500 units